



Government of the Republic of Trinidad and Tobago
Ministry of Sport and Youth Affairs

MEMORANDUM

TO: All Tenderers
FROM: Administrative Officer II, Procurement Unit
DATE: 3rd May, 2019
SUBJECT: **Addendum 1 – Proposed Construction of New Perimeter Fencing (Pasture Development) at the Chatham Youth Development and Apprenticeship Center**

This addendum is issued prior to the close of tenders.

Further to the **Mandatory Site Briefing and Site Visit** conducted on **Wednesday 1st May, 2019 at 10:00 a.m.**, at the Chatham Youth Development and Apprenticeship Center, for the Proposed Upgrade of Dormitories, Tenderers are advised of the following:

1. Please replace See Revised “Works To Be Done” section attached, which supersedes existing. As a result, please replace existing “Works To Be done”, originally issued in Tender Package, in its entirety.
2. To note that the **Closing Date and Time** for the submission of tenders remains as **Monday 13th May, 2019 at 10:00 a.m.**
3. **Tenderers are ALSO advised, to Please note this document officially forms part of your tender package and is to be attached and submitted (In its entirety) as part of your proposal.**

Respectfully,

Administrative Officer II
Procurement Unit
/f/Permanent Secretary
Ministry of Sport and Youth Affairs

We hereby acknowledge receipt of the above referenced Addendum #1 which shall be incorporated into our Tender submission.

Name of Tenderer’s Company:

Name/Title [print]:

Signature of Authorized Tenderer’s Representative:

REVISED WORKS TO BE DONE

NOTES:

- (i) Dimensions and quantities stated are approximate. Tenderers are to visit the site and verify all dimensions and quantities, existing conditions and prices should include for these.
- (ii) The descriptions below are to be read in conjunction with the relevant specifications in the materials and workmanship section
- (iii) The contractor may include in the price of the measured work Nr. any considerations arising from said specifications

REVISED WORKS TO BE DONE

Item	Description	Qty.	Unit	Rate	Cost
	FENCING				
A.	Remove overgrown and overhanging vegetation from fencing, 1m clearance either side.		Item		
B.	Remove existing barb wire fence and chain link fence and dispose appropriately offsite.		Item		
C.	Allow a Provisional Sum of \$2,500.00, for remedial works on steel fence posts.		Allow.		2,500.00
D.	Install 10gauge. barbed wire strung in horizontal and diagonal lines, fixed to posts in notches and tensioned at centres::				
	i. 3m	152	m		
	ii. 4m	410	m		
E.	Install 10gauge chain link fencing 1.2 metres high comprising 50mm square woven wire mesh tied with galvanized soft iron wire to outside of existing posts and including three (3) 10gauge straining wire with 1½ Nr pair of 400mm eye bolt and turn buckle, at centres:				
	i. 3m	152	m		
	ii. 4m	410	m		
F.	Protection of all works in this section.		Item.		
	TO GENERAL SUMMARY S				