



Government of the Republic of Trinidad and Tobago
Ministry of Sport and Youth Affairs

MEMORANDUM

TO: All Tenderers
FROM: Administrative Officer II, Procurement Unit
DATE: 7th May, 2019
SUBJECT: Addendum 1 – Proposed Sewer Upgrades at California Youth Facility, Point Lisas

This addendum is issued prior to the close of tenders.

Further to the **Mandatory Site Briefing and Site Visit** conducted on **Friday 3rd May, 2019 at 3:00 p.m.**, at the California Facility, for the Proposed Sewer Upgrades, Tenderers are advised of the following:

1. Please see “Revised Works to be Done” attached, which supersedes existing. As a result, please replace existing “Works To Be done” section, originally issued in Tender Package, in its entirety.
2. To note that the **Closing Date and Time** for the submission of tenders remains as **Wednesday 15th May, 2019 at 3:00 p.m.**
3. **Tenderers are ALSO advised, to Please note this document officially forms part of your tender package and is to be attached and submitted (In its entirety) as part of your proposal.**

Respectfully,

.....
Administrative Officer II
Procurement Unit
/f/Permanent Secretary
Ministry of Sport and Youth Affairs

We hereby acknowledge receipt of the above referenced Addendum #1 which shall be incorporated into our Tender submission.

Name of Tenderer’s Company:

Name/Title [print]:

Signature of Authorized Tenderer’s Representative:

REVISED WORKS TO BE DONE Cont'd

Item	Description	Qty.	Unit	Rate	Cost
NEW CESSPIT TANK AND SOAK-A-WAY					
<u>Cesspit Tank</u>					
A.	Excavate to receive new cesspit tank and cart away unused soil off site.		Item		
B.	Erect cesspit slab as shown on drawings attached.		Item		
C.	Erect 6" thk. concrete walls with 5/8" starter bars one (1) in every core, filled with 3,000 psi insitu concrete to top of wall, along with 6" thk. reinforced baffle wall.		Item		
D.	Construct cesspit tank cover using, in two (2) equally separated parts, 3" thk. reinforced with 65 BRC Fabric and 1/2" bars 1'- 0" c/c, along with four (4) No. 3/8" diameter bars for handles, as shown on drawings attached.		Item		
<u>Soak-A-Way</u>					
E.	Excavate to receive soak-a-way and cart away soil off site.		Item		
F.	Fill excavated area with earthen materials in layers as shown on drawings attached.		Item		
G.	Lay a 4' - 0" x 4' - 0" x 3" thk. concrete reinforced slab oven soak-a-way as shown on drawings attached.		Item		
H.	Allow for the protection of all works in this section.		Item		
TO SUMMARY \$					

REVISED WORKS TO BE DONE Cont'd

Item	Description	Qty.	Unit	Rate	Cost
	PLUMBING INSTALLATIONS				
A.	Insert 4" diameter schedule 40 PVC pipes to inlet and outlet of cesspit tank as shown on drawings attached.		Item		
	EXISTING CESSPIT TANK AND SOAK-A-WAY				
B.	Clean existing cesspit tank and "snake" all lines to water closets.		Item		
C.	Excavate new soak-a-way to service existing cesspit tank and cart away soil offsite.		Item		
D.	Fill excavated area with earthen materials in layers as shown on drawings attached.		Item		
E.	Allow a provisional sum of \$12,000.00 for all additional plumbing works in this section.		Allow		12,000.00
F.	Allow a provisional sum of \$10,000.00 to make all existing works good.		Allow		10,000.00
	TO SUMMARY \$				

